



Evergy  
1200 Main Street  
Kansas City  
Missouri 64105  
Evergy.com

To: Jared Morrison, Director  
Waste and Water Programs

Project:  
Liner Design Criteria  
Iatan Ash Impoundment

From:  
Jay Martin, P.E.  
Evergy

## Memorandum

Subject: Iatan Ash Impoundment Liner Design Criteria

### CCR Unit Status and Regulatory Explanation:

The Iatan Generating Station Ash Impoundment is subject to the requirements of §257.71 which addresses the requirements for liner documentation for CCR surface impoundments. A surface impoundment is considered a "lined" surface impoundment if constructed with:

- i. A liner consisting of a minimum of two feet of compacted soil with a hydraulic conductivity of no more than  $1 \times 10^{-7}$  cm/sec;
- ii. A composite liner that meets the requirements of §257.70(b); or
- iii. An alternative composite liner that meets the requirements of §257.70(c).

The Iatan Ash Impoundment is considered unlined primarily due to the lack of documentation supporting the "as built" clay liner materials, therefore is considered an unlined CCR surface impoundment.

